
iScaf Quoting System

Description :
Prepared For :
Quote Date : Wed Nov 22 2006
Period : 1 Weeks 0 Days
Deliveries : NONE
Stages : NONE
Levels : NONE
Job #
Quotation #
Linear # 20.8 m
Area # 124.7 m2
Volume # 158.2 m3
Reference # ANDREW-NEW\C:\drawings\sample10.dwg

Contact :
Site Address :
:
:
Phone #1 : -()
FAX #1 : -()
Phone #2 : -()
FAX #2 : -()

Stock Code	Description	D	S	L	QTY	WEIGHT	AMOUNT
BOARD2	Hopups 2 Board Bracket	0	0	0	10	60.0	7.80
BRACE36	Diagonal Brace 3.6 meter	0	0	0	8	124.8	6.24
DCOUP	Double Coupler	0	0	0	16	16.0	3.52
JACK	Screw Jack	0	0	0	20	150.0	15.00
LED12	Guard Rail Ledgers 1.2 meter	0	0	0	10	50.0	5.00
LED24	Guard Rail Ledgers 2.4 meter	0	0	0	80	800.0	49.60
SOLE	Sole Board	0	0	0	20	54.0	7.40
STAN2	Standard 2.0 meter	0	0	0	20	250.0	17.60
STAN3	Standard 3.0 meter	0	0	0	30	495.0	36.90
STEEL12	Steel Kwikboards 1.2 meter	0	0	0	8	68.0	5.52
STEEL24	Steel kwikboards 2.4 meter	0	0	0	64	1024.0	67.20
TIE12	Tie Bars 1.2 meter	0	0	0	1	3.0	0.29
TIE24	Tie Bars 2.4 meter	0	0	0	8	48.0	2.48
TRAN12	Transoms 1.2 meter	0	0	0	40	380.0	22.00
TUBE06	Tube 0.6 meter	0	0	0	8	24.8	0.88
TUBE24	Tube 2.4 meter	0	0	0	4	50.0	1.84
Sub Total					347	3597.6	\$ 249.27

Period : 1 Weeks 0 Days

Total \$ 249.27